

Bid Tabulation

City of Van Wert Woodland Avenue Paving Project June 1, 2017

VTF Excavation LLC Celina, Ohio

Helms & Sons Excavating Findlay, Ohio

DEE	1755.4		LINUT OF	4.000.01/	LIBUT	Julie 1, 2017	LIBUT	CCIIIIA, OTIIO	LIBIT	Tiridiay, Offic
	ITEM	DESCRIPTION	UNIT OF	APPROX.	UNIT	TOTAL	UNIT	TOTAL	UNIT	TOTAL
<u>NO.</u>		<u>DESCRIPTION</u>	<u>MEASURE</u>	<u>QTY.</u>	<u>COST</u>	COST	<u>COST</u>	COST	COST	COST
1	201	CLEARING AND GRUBBING, AS PER PLAN	LUMP	1	\$1,000.00	\$1,000.00	\$10,665.03	\$10,665.03	\$15,222.82	\$15,222.82
2	202	TREE REMOVED	EACH	7	\$1,000.00	\$7,000.00	\$704.01	\$4,928.07	\$808.65	\$5,660.55
3	202	REMOVED, AS PER PLAN	LUMP	1	\$2,000.00	\$2,000.00	\$3,155.36	\$3,155.36	\$2,154.20	\$2,154.20
4	202	PIPE REMOVED, 24" AND UNDER	FT.	18	\$20.00	\$360.00	\$26.69	\$480.42	\$33.88	\$609.84
5	202	PAVEMENT REMOVED	S.F.	1614	\$5.00	\$8,070.00	\$0.56	\$903.84	\$1.50	\$2,421.00
6	202	CURB REMOVED	FT.	1508	\$7.00	\$10,556.00	\$4.23	\$6,378.84	\$7.31	\$11,023.48
7		WALK REMOVED	S.F.	2307	\$2.00	\$4,614.00	\$2.21	\$5,098.47	\$1.11	\$2,560.77
8		CATCH BASIN REMOVED	EACH	1	\$400.00	\$400.00	\$213.05	\$213.05	\$392.94	\$392.94
9		EXCAVATION INCLUDING EMBANKMENT CONSTRUCTION, AS PER PLAN	C.Y.	1577	\$10.00	\$15,770.00	\$12.67	\$19,980.59	\$15.59	\$24,585.43
10		SUBGRADE COMPACTION, AS PER PLAN	S.Y.	5053	\$3.00	\$15,159.00	\$0.74	\$3,739.22	\$1.03	\$5,204.59
			C.Y.							
11		EXCAVATION OF SUBGRADE AND STRUCTURAL EMBANKMENT, AS PER PLAN		560	\$40.00	\$22,400.00	\$45.51	\$25,485.60	\$54.76	\$30,665.60
12		1-1/2" PAVEMENT PLANING, ASPHALT CONCRETE	S.Y.	14347	\$2.00	\$28,694.00	\$1.94	\$27,833.18	\$2.21	\$31,706.87
13		3" ASPHALT CONCRETE BASE, PG64-22	C.Y.	411	\$150.00	\$61,650.00	\$173.66	\$71,374.26	\$155.53	\$63,922.83
14		AGGREGATE BASE, AS PER PLAN	C.Y.	422	\$35.00	\$14,770.00	\$32.87	\$13,871.14	\$37.10	\$15,656.20
15		TACK COAT FOR INTERMEDIATE COURSE	GAL.	1543	\$4.00	\$6,172.00	\$2.35	\$3,626.05	\$2.03	\$3,132.29
16	407	TACK COAT, 0.08 GAL/S.Y.	GAL.	1532	\$4.00	\$6,128.00	\$2.35	\$3,600.20	\$2.03	\$3,109.96
17	411	STABILIZED CRUSHED AGGREGATE	C.Y.	486	\$40.00	\$19,440.00	\$32.28	\$15,688.08	\$37.10	\$18,030.60
18	441	3" ASPHALT CONCRETE SURFACE, TYPE 1, (448), PG64-22 (DRIVEWAY)	C.Y.	14	\$300.00	\$4,200.00	\$469.34	\$6,570.76	\$270.89	\$3,792.46
19	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (448)	C.Y.	417	\$170.00	\$70,890.00	\$188.91	\$78,775.47	\$177.02	\$73,817.34
20	441	1-1/4" ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448) PG64-22	C.Y.	665	\$190.00	\$126,350.00	\$193.60	\$128,744.00	\$172.59	\$114,772.35
21	441	1/2" ASPHALT CONCRETE LEVELING COURSE, TYPE 1	C.Y.	186	\$200.00	\$37,200.00	\$210.03	\$39,065.58	\$172.60	\$32,103.60
22	452	6" NON-REINFORCED CONCRETE PAVEMENT, AS PER PLAN	S.Y.	757	\$50.00	\$37,850.00	\$62.90	\$47,615.30	\$57.24	\$43,330.68
23		4" SHALLOW PIPE UNDERDRAINS, 707.31 (PERFORATED), AS PER PLAN	FT.	1232	\$9.00	\$11,088.00	\$6.53	\$8,044.96	\$7.08	\$8,722.56
24		4" CONCRETE WALK	S.F.	922	\$8.00	\$7,376.00	\$5.93	\$5,467.46	\$5.59	\$5,153.98
25		CURB RAMPS, WITH TRUNCATED DOMES, AS PER PLAN	S.F.	1755	\$12.00	\$21,060.00	\$10.15	\$17,813.25	\$9.09	\$15,952.95
		CURB REPLACED IN-KIND	5.1 . FT.	377	\$12.00	\$7,540.00	\$33.83	\$12,753.91	\$28.50	\$10,744.50
26										
27		COMBINATION CURB AND GUTTER, TYPE 2, AS PER PLAN	FT.	1232	\$20.00	\$24,640.00	\$17.44	\$21,486.08	\$16.95	\$20,882.40
28		4" CONDUIT, TYPE B, 707.45, STORM REPAIR, AS PER PLAN	FT.	50	\$20.00	\$1,000.00	\$12.26	\$613.00		\$414.00
29		6" CONDUIT, TYPE B, 707.45, STORM REPAIR, AS PER PLAN	FT.	50	\$20.00	\$1,000.00	\$15.89	\$794.50	\$11.29	\$564.50
30		8" CONDUIT, TYPE B, 707.45, STORM REPAIR, AS PER PLAN	FT.	50	\$25.00	\$1,250.00	\$19.12	\$956.00	\$15.04	\$752.00
31	611	12" STORM SEWER, AS PER PLAN	FT.	644	\$50.00	\$32,200.00	\$54.52	\$35,110.88	\$62.26	\$40,095.44
32	611	6" STORM SEWER, AS PER PLAN	FT.	19	\$30.00	\$570.00	\$24.39	\$463.41	\$57.16	\$1,086.04
33	611	TYPE 1 CATCH BASIN, AS PER PLAN	EACH	9	\$2,200.00	\$19,800.00	\$2,243.96	\$20,195.64	\$1,633.48	\$14,701.32
34	611	TYPE 2-2B CATCH BASIN, AS PER PLAN	EACH	18	\$2,000.00	\$36,000.00	\$1,517.69	\$27,318.42	\$1,377.53	\$24,795.54
35	611	MANHOLE RECONSTRUCTED TO GRADE, AS PER PLAN	EACH	1	\$1,200.00	\$1,200.00	\$997.35	\$997.35	\$2,138.62	\$2,138.62
36	611	CATCH BASIN ADJUSTED TO GRADE	EACH	23	\$500.00	\$11,500.00	\$222.26	\$5,111.98	\$404.08	\$9,293.84
37	611	MANHOLE ADJUSTED TO GRADE	EACH	34	\$650.00	\$22,100.00	\$938.68	\$31,915.12	\$1,150.86	\$39,129.24
38	611	TYPE D SANITARY SEWER MANHOLE, AS PER PLAN	EACH	2	\$5,000.00	\$10,000.00	\$7,520.09	\$15,040.18		\$13,921.78
39		4" SANITARY SEWER LATERAL	FT.	20	\$40.00	\$800.00	\$39.27	\$785.40	\$91.05	\$1,821.00
40		8" SANITARY SEWER, AS PER PLAN	FT.	123	\$80.00	\$9,840.00	\$44.39	\$5,459.97	\$80.14	\$9,857.22
41		15" SANITARY SEWER, AS PER PLAN	FT.	10	\$120.00	\$1,200.00	\$154.27	\$1,542.70		\$2,547.20
41		18" SANITARY SEWER, AS PER PLAN	FT.	10	\$120.00	\$1,500.00	\$134.27	\$2,027.50		\$2,636.30
43		SANITARY MANHOLE ADJUSTED TO GRADE, NEW FRAME AND CASTING	EACH	5	\$1,000.00	\$5,000.00	\$1,278.45	\$6,392.25		\$5,754.25
44		MAINTAINING TRAFFIC	LUMP	1	\$10,000.00	\$10,000.00			\$14,529.71	\$14,529.71
45		COMPACTED AGGREGATE	C.Y.	172	\$40.00	\$6,880.00	\$46.18	\$7,942.96	\$47.69	\$8,202.68
46		REMOVAL OF GROUND MOUNTED SIGN AND RELOCATION	EACH	9	\$500.00	\$4,500.00	\$124.28	\$1,118.52	\$65.00	\$585.00
47		REMOVAL OF GROUND MOUNTED POST AND DISPOSAL	EACH	8	\$20.00	\$160.00	\$46.61	\$372.88	\$25.00	\$200.00
48		STREET NAME SIGN SUPPORT, NO. 3 POST	FT.	12	\$40.00	\$480.00	\$14.08	\$168.96	\$12.00	\$144.00
49	630	GROUND MOUNTED SIGN SUPPORT, NO. 3 POST	FT.	98	\$40.00	\$3,920.00	\$11.73	\$1,149.54	\$10.00	\$980.00
50	638	VALVE BOX ADJUSTED TO GRADE	EACH	8	\$200.00	\$1,600.00	\$74.09	\$592.72	325.46	\$2,603.68
51	638	WATER WORKS, MISC.: 6" WATER MAIN RELOCATED, AS PER PLAN	FT.	50	\$80.00	\$4,000.00	\$50.60	\$2,530.00	210.64	\$10,532.00
52	638	WATER WORKS, MISC.: 8" WATER MAIN RELOCATED, AS PER PLAN	FT.	50	\$90.00	\$4,500.00	\$51.59	\$2,579.50	258.13	\$12,906.50
53	638	WATER WORKS, MISC.: WATER MAIN RECONNECTED, AS PER PLAN	EACH	2	\$600.00	\$1,200.00	\$421.78	\$843.56	\$1,652.45	\$3,304.90
54		STOP LINE	FT.	28	\$10.00	\$280.00	\$11.73	\$328.44	\$10.00	\$280.00
55		RAILROAD CROSSING	EACH	2	\$500.00	\$1,000.00	\$469.34	\$938.68	\$400.00	\$800.00
56		SEEDING AND MULCHING, CLASS 1, AS PER PLAN	S.Y.	1213	\$3.00	\$3,639.00	\$6.95	\$8,430.35	\$6.34	\$7,690.42
57	861	GEOGRID, AS PER PLAN	S.Y.	1012	\$5.00	\$5,060.00	\$4.01	\$4,058.12	\$3.94	\$3,987.28
58	SPEC	MAILBOX REMOVED AND REST	EACH	2	\$250.00	\$500.00	\$186.42	\$372.84	\$94.49	\$188.98
		TOTAL				\$775,056.00		\$793,706.39		\$801,776.23